



INSPECTIONS AND COMPLIANCE CHALLENGES

Commencement Notice and Construction Stage

Mariola Heksel

MSc MIEI

Acting Executive Engineer

Building Control Section Kildare County Council




Kildare County Council Building Control (BC) Structure:

Building Control Staff 4.5 Full time equivalent (Fte)

- ½ (fte) Senior Executive Engineer
- 2 (fte) Building Control Officers (BCO)
- 2 (fte) Administrative Staff members

Building Control Staffing



- Time allocations: week on BCMS or Site

- While managing the BCMS activities (notices, applications, CCC, DACs),
- We also deal with day-to-day queries and complaints which we received.

Kildare County Council Building Control submissions and inspections in 2022


Total Number of valid submission 2022:

- ▶ Commencement Notice - **554**
- ▶ Certificate of Compliance on Completion – **736**
- ▶ Disability Access Certificate - **216**

Number of inspections in 2022 on new buildings – **990**

NOAC – **53.11%**

KCC Building Control Statistics



Assessing Commencement Notices in accordance with Article 10 for validation:

Check List:

- CN Date
- Statutory Document
- Project Particulars
- Online Assessment
- Fee amount correct
- Schedule of Documents
- Preliminary Inspection Plan if applicable
- Site Location Map
- Construction Drawings

- Desktop technically assessment completed in 2022 and 2023- **498**
- Number of Section 11 requested following desktop technical assessment in 2022 and 2023 – **45**

Common Additional information request at validation stage

1. CN statutory forms are not correct (date, signature, description).
2. Inadequate design details or calculations to show compliance with Building Regulations
 - Part A
 - Part B
 - Part C
 - Part F
 - Part L and ACD

Commencement Notice with Opt Out Declaration - Proposed two storey house



Edit			
Project Particulars Online Assessment Phasing Nominate Roles Statutory Forms Payment Validation			
Commencement Date:	25/09/2023	Status:	Revised Information
Information required:	Please provide the following Information: 1. Provide a full set of construction drawings for the works as described in the commencement notice, drawings to include: 1.1. Site Location Map 1.2. Proposed site layout 2. A full pack of construction details e.g., the following items and other important junctions: 2.1. Roof eaves and apex details (please include roof ventilation details) 2.2. Roof details 2.3. Wall details, to include cavity wall ope head, jamb and cill details and insulation details (please include all cavity trays, weep holes etc where applicable) 2.4. External wall movement joint detail (if required) 2.5. Foundation details (width, depth, reinforcement, concrete strength) 2.6. Floor slab details (type of fill, radon barrier, insulation, floor slab, etc) 3. Please upload proof of payment.	Information Required by:	21/09/2023

Inadequate design information

Sample Revised information request for Part A Building Regulation

Walls: (Full Fill Insulation)

- Please review the Acceptable Construction Details for Thermal, Vapour and Airtightness requirements for all major external wall construction methods.
- Please take note of a few key points to note:
 - a. Standard wall ties at 450mm Vertical and Horizontal centres
 - b. Corner DPC
 - c. Hockey Stick & Meter Box Board details
 - d. Doubling up of wall ties around opening (450 c/c vertical) and @ roof verges.
 - e. Stepped cavity trays, weep holes in both brickwork and render finishes.
- Please call up wall ties, note, for 'Standard' wall ties (+900N), SR 325 would require these to be installed at 4.9 per m², 450mm Vertical and *450mm Horizontal centres.
- Stepped cavity trays, weep holes in both brickwork and render finishes @ 1000mm centres as per SR 325 5.5.5.2
- Render to SR 325 (Design Item)
- Mortar to SR 325 (Design Item)




Inadequate design information

Sample Revised information request for Part B Building Regulation

First Floor:

- Where timber floors are proposed, please see 'Supplementary Guidance to Technical Guidance Document B (Fire Safety) Volume 2 - Dwelling Houses'.
- Note, all penetrations into floor void require fire stopping, even services going into the floor void through the head of a timber stud wall and through plasterboard (light fixtures etc).
 - a. Below 40mm dia, use intumescent mastic.
 - b. Above 40mm dia, fire collar or trap wrap required. Note, all collars and wraps have to be restrained to allow the fire stop to collapse inwards on itself.
 - c. All to be installed to the manufacturer's recommendation.



FIRST FLOOR



Structural grade C16 225 x 44mm timber floor joists @ 400mm ccs including associated timber bridging, hangers, straps and connections
150mm thick Isover acoustic roll insulation installed between floor joists throughout

Inadequate design information

Sample Revised information request for Part C Building Regulation

Foundation:

- Fill below ground as per TGD C Diagram 4, Par 3.1.4 (TDG C)
- Note, fill near rising walls to be as per point noted above, i.e. Under footpaths.
- Ensure radon membrane is installed to the manufactures Irish Agreement Cert and CP 102.
- Rebar cover to foundation which are poured onto the natural ground is 75mm.
- Blockwork: Rising Blockwork to comply with *I.S. EN 771-3*. Strength to Engineers design



Inadequate design information

Sample Revised information request for Part F Building Regulation.

Dwelling Ventilation:

If natural, please review Table 3 in TGD F for ventilation requirements for rooms, however, individual vents in each room may not be enough for 'Whole House Ventilation'. Please review Example 4 in TGD F for a naturally vented house. Remember, Minimum room provisions shown below might not be enough for the whole house design.

Centralized Continuous Mechanical Extract Ventilation & Centralized Mechanical Ventilation with Heat Recovery require design input before installation takes place.

Note, critically for Mechanically Vents Dwellings, on completion, the ventilation system has is required be tested and commissioned by a competent independent third party and is deemed to validate that a ventilation system has been installed.

Room or Space	General Ventilation	Extract ventilation	Purge ventilation
	Minimum equivalent area of background ventilator ^a (mm ²)	Extract fan ^b - Minimum intermittent extract rate (l/s) ^h	Opening window or external door - Minimum provision ^g
Habitable Room	7000 ^{c,d}	-	1/20th of room floor area
Kitchen	3500 ^{c,d,f}	60 l/s generally 30 l/s if immediately adjacent to cooker (e.g. cooker-hood not recirculating)	Window opening section (no size requirement) ^d
Utility Room	3500 ^{c,d}	30 l/s	Window opening section (no size requirement) ^d
Bathroom	3500 ^{c,d}	15 l/s	Window opening section (no size requirement) ^d
Sanitary Accommodation (no bath or shower)	3500 ^{c,d}	6 l/s ^e	Window opening section (no size requirement) ^d

- Notes:
- (a) See paragraph 1.2.4.1 re: total equivalent area for all background ventilators.
 - (b) See paragraphs 1.2.4.9 and 1.2.4.10 re alternative of passive stack ventilation or continuous room ventilation with heat recovery.
 - (c) See paragraph 1.2.4.12 re the extent and location of background ventilation where there is only a single exposed façade and cross-ventilation is not possible.
 - (d) See paragraph 1.2.4.3 re ventilation provision where the provision of background ventilation and purge ventilation is not possible, e.g. when there is no external wall.
 - (e) As an alternative, the opening window section provided for purge ventilation may also be relied on for extract ventilation.
 - (f) See paragraphs 1.2.4.13 to 1.2.4.15 re: provision for ventilation of habitable rooms through other rooms or into courtyards.
 - (g) Opening window or external door minimum provisions given in this table are for ventilation purposes. Other requirements apply to the provision of openings for windows or external doors for example escape in case of a fire. Refer to Part B / TGD B for further guidance.
 - (h) The performance flowrates for Intermittent extract fans should be tested in accordance with I.S. EN 13141-4:2011, Cooker Hood performance flowrates should be measured in accordance with I.S. EN 13141-3:2017.

Inadequate design information

Sample Revised information request for Part L Building Regulation and ACD.



Heating System - Energy Requirements (Individual)

Main space heating system efficiency [%]	546.98	Space heating efficiency adjustment factor	1.0000	Main space heating fuel efficiency [%]	
Main water heating system efficiency [%]	273.31	Water heating efficiency adjustment factor	1.0000	Main water heating fuel efficiency [%]	
Secondary heating system efficiency [%]	NA	Fraction of heating from secondary heating system	NA	Secondary space heating system fuel	
Fraction of main space and water heat from CHP	NA	Electrical efficiency of CHP	NA	Heat efficiency of CHP	
CHP Fuel type	NA				

Summary for Part L Conformance (Applies to TGD L 2008/2011/2019 for new dwell)

BER Number		Building Regulations	2011
BER Result	A2	Energy Value kWh/m ² /yr	34.7
CO ₂ emissions [kg/m ² /yr]	4.44		
EPC	0.243	EPC Pass/Fail	Pass
CPC	0.157	CPC Pass/Fail	Pass

Part L Conformance - Fabric

Conformity with Maximum avg U-value requirements	U-value [W/m ² K]	Pass/Fail	Conformity with Maximum U-value requirements	U-Value [W/m ² K]
Pitched roof insulated on ceiling	0.16	Pass	Roofs	0.19
Pitched roof insulated on slope	0.17	Fail	Walls	0.19
Flat Roof	0.19	Pass	Floors	0.18
Floors with no underfloor heat	0.14	Pass	External doors / windows / rooflights	1.40
Floors with underfloor heat	0.00	Pass	Meets Part L maximum avg U-value requirement for opaque elements using TGD L Section 1.3.2.3	
Walls	0.18	Fail		
Percentage of opening areas [%]	26.29			
Average U value of openings	1.40	Pass		

Permeability test carried out and meets guidelines in TGD L

Date report

(1) WALLS:- INSULATION IN CAVITY Roofs DETAIL 1.10, 2011

<p>THERMAL PERFORMANCE</p> <p>Ensure continuity of insulation throughout junction</p> <p>Ensure full depth of insulation between and over joints abuts eaves insulation</p> <p>Ensure gap between wall plate and proprietary eaves vent is completely filled with insulation having a min. R-value across the insulation thickness of 3.00 m²K/W</p> <p>Ensure full fill insulation is secured firmly against inner leaf of cavity wall. If using partial fill insulation, tuck compressible insulation down into the head of the cavity</p> <p>Detail is indicative for thermal purposes. Where continuity of insulation is maintained throughout the junction, alternative structural design may be used.</p>	<p>CHECKLIST (TICK ALL)</p> <p><input type="checkbox"/></p> <p><input type="checkbox"/></p> <p><input type="checkbox"/></p> <p><input type="checkbox"/></p> <p><input type="checkbox"/></p> <p><input type="checkbox"/></p>	<p>AIR BARRIER - CONTINUITY</p> <p>CHECKLIST (TICK ALL)</p> <p><input type="checkbox"/> Bed wall plate on continuous mortar bed</p> <p><input type="checkbox"/> Fix ceiling first, and seal all gaps between ceiling and masonry wall with either plaster, adhesive or flexible sealant</p> <p><input type="checkbox"/> Seal all penetrations through air barrier using a flexible sealant</p> <p>Complying with checklist will help achieve design air permeability</p>
---	--	--

GENERAL NOTES

Thermal performance of junction can be improved by incorporating an eaves wind barrier (guywood, OSB, softboard or other suitable material) around insulation to be sealed to connect with the ventilator strip thereby mitigating wind chill from the wall/ink in the eaves

Keep cavities clean of mortar snots and other debris during construction.

Use of over joint insulation is considered best practice, as it eliminates the cold bridge caused by the joint

Use a proprietary eaves ventilator to ensure ventilation in accordance with BS5250. Insulation of the eaves ventilator must not prevent free water drainage below the tilting battens

Ensure cavity is closed with fleecing/insulant or proprietary cavity barrier

ACCEPTABLE CONSTRUCTION DETAIL Eaves - Ventilated Attic

<p>GENERAL NOTES</p> <p>The wall insulation installed below the wall DPC must be fit for purpose with regards to water absorption.</p> <p>Keep cavities clean of mortar snots and other debris during construction.</p> <p>Detail applicable:- Ground-bearing floor; raft foundation; in-situ suspended ground floor slab; pre-cast suspended ground floor. Insulation above slab, with timber floor finish.</p>	<p>OPTION (TICK ONE)</p> <p>AIR BARRIER - OPTIONS</p> <p><input type="checkbox"/> Masonry inner leaf with wet-finish plaster, or</p> <p><input type="checkbox"/> Masonry inner leaf with scratch coat and finished with plasterboard, or</p> <p><input type="checkbox"/> Inner leaf with plasterboard on dabs, with continuous ribbon of adhesive tape around all openings, along top and bottom of wall, and internal and external corners, or</p> <p><input type="checkbox"/> Airtightness membrane and tapes</p>	<p>AIR BARRIER - CONTINUITY</p> <p>CHECKLIST (TICK ALL)</p> <p><input type="checkbox"/> Seal between wall and floor air barrier with a flexible sealant OR seal gap between skirting board and floor with a flexible sealant</p> <p><input type="checkbox"/> Seal all penetrations through air barrier using a flexible sealant</p> <p>Complying with checklist will help achieve design air permeability</p>
---	---	---

75mm screed, 150mm slab thermal conductivity w/mK

KCC Risk Procedure on selection of buildings or works to inspect

Development Factors

1. New Build – Multi-unit residential up to 2 storeys high? Y N
2. New Build – Multi storey developments between 2-3 storeys high? Y N
3. New Build – Multi storey developments 3 storeys and above? Y N
4. Does the Building require a specialist fire engineering design? Y N
5. Does the Building require a specialist foundation design? Y N
6. Does the development require a change of use to higher risk (e.g. from commercial to Residential or emergency accommodation etc) Y N
7. Are non-conventional or modern methods of construction (e.g., ICF, Modular construction etc) being used on this development? Y N
8. Building Owners, Builders and Assigned Certifiers track record. Have any previous S11 requests or Section 8 Enforcement notices been served on previous developments? Y N

Table 2.0: Development Risk Rating Identification

		Risk Rating Identification				
Development Factors Total		1	2	<4	<6*	<8
On Site Building Inspection Target	Optional – On site BC inspections	Very Low				
	On site BC inspection frequency <8weeks		Low			
	On site BC inspection frequency <6 weeks			Medium		
	On site BC inspection frequency <4 weeks				High	
	On site BC inspection frequency <2 weeks					Very High

*If Development Factor 8 is applicable the risk defaults to at least "High"


Table 1.0: Worked Example (Development Factors)

Development Factor	Y/N	Score
1	Y	1
2	Y	1
3	N	0
4	N	0
5	N	0
6	N	0
7	N	0
8	N	0
Total		2

KCC site inspection procedure

- ▶ Notify Building Owner, Assigned Certifier, Designer and the Builder of Building Control inspection.
- ▶ Review the drawings, site plans and other relevant document submitted.
- ▶ Appropriate PPE to be worn (safe pass, delegation, etc.).
- ▶ Comply with site safety procedures (site induction).
- ▶ Inspections of critical items or at critical milestones in the construction process to check for compliance with Regulations A to M.
- ▶ Record site inspection.
- ▶ If compliance issues is identified, then depending on the issue it might be closed out by email with photographic evidence that work has been completed in compliance or by requesting additional information by Section 11 request under Building Control Act
- ▶ Follow up inspection might be required.
- ▶ All addition information is uploaded to KCC file and BCMS.



 **BUILDING CONTROL - SITE INSPECTION RECORD**
SECTION 11 (3), BUILDING CONTROL ACTS, 1990 to 2014

DC No. _____ Site Name & Address: _____
Building Control Inspector: _____ Date & Time of Inspection: _____
CN No / Nos. _____

Inspection Category:
Risk Based: Random Base: Non-Technical Building Control Inspection
Complaint Based: Site-Follow-Up due to Complaint or Non Compliance:
Inspection Related to Statutory Applications: Site Progress Inspection:

Inspection Type:
Commencement Notice Inspection: General BC Inspection: CCC: DAC:
Site Progress Inspection: No Access / Site Closed: FC: FP:

Current Stage of Works: _____
Unit Names / No's Inspected: _____
Person in Charge of Site: _____
Level of Construction Supervision on Site: _____
Scope of Inspection if applicable: _____

Issues or Findings Arising at time of inspection: _____

A B C D E F G H J K L M

Please tick relevant box for technical inspections

Follow Up Action (If Any): _____

Persons Accompanying: _____
Name of Authorised Person: _____ Signature: _____



Page 1 of _____

Typical Non-Compliance Issues found in KCC

Superstructure:

Cavity Wall Construction - Wall Ties


SR 325 Design of Masonry in Ireland E6



9. Declared Performance:

Essential Characteristics	Performance			Technical Specification
RANGE				
	WTS2 200 to 275	WTS3 200 to 300	WTS4 200 to 275	
MECHANICAL STRENGTH & STIFFNESS				
Tensile Strength (N)	1800	1100	650	EN 845-1 clause 5.3.1.2; EN 846-5
Displacement Under Load ^[1] (mm)	0.23	0.09	0.18	EN 845-1 clause 5.3.1.4
Compressive Strength (N)	1300	800	450	EN 845-1 clause 5.3.1.3; EN 846-5
Displacement Under Load ^[1] (mm)	0.14	0.18	0.11	EN 845-1 clause 5.3.1.4
Water Shedding Capability	RESISTANT			EN 845-1 clause 5.4
DURABILITY				
Material	Stainless Steel Grades: 1.4301, 1.4597			EN 10088-2
Corrosion Protection	Material/Coating Reference: 03			EN 845-1 Table A.1
Dangerous Substances	None			


^[1] At 1/3 of Declared Tensile & Compressive Strength



Typical Non-Compliance Issues found in KCC

Superstructure:

First Floors - Fire Penetrations



B

Fire Safety
Volume 2
Dwelling Houses

Building Regulations 2017

Supplementary Guidance to TGD B (Fire Safety) Volume 2- Dwelling Houses 2017

Guidance on Fire Resistance of Walls, Intermediate Floors, and Trussed Roofs in dwellings

Technical Guidance Document

Riailtas na hÉireann
Government of Ireland

An Boinn Tithíochta, Pleanála, Pobail agus Rialtais Ábhaí
Department of Housing, Planning, Community and Local Government

Prepared by the Department of Housing, Planning and Local Government
Housing Unit

Typical Non-Compliance Issues found in KCC


Substructure:

1. Fill - T3, T2, T1 & T0


2. Radon CP102

Table 3 Minimum Performance Level for LDPE Radon Proof Membranes		
Parameter	Test	Performance Level
Radon Permeability	Laboratory Test with Radon Gas – Rn-222	12*10 ⁻¹⁰ -12m ² /s
Tensile Strength	I.S. EN 12311-2:2000, or I.S. EN ISO 527-3	MD > 12Mpa CD > 12Mpa
Elongation	I.S. EN 12311-2:2000, or I.S. EN ISO 527-3	≥100% (at break) Un-reinforced LDPE ≥12% (at max. load) Reinforced LDPE
Tear Resistance	I.S. EN 12310-2:2000	>100N
Moisture Vapour Resistance	BS 3177	>50MN/g
Low Temperature Flexibility	I.S. EN 495-5:2000	No cracking at -25 °C

Membranes used for Radon protection will normally be provided in lieu of the damp-proof membranes described in Section 3 of this document.



Residential Detail (Radon Sump present)



Rialtas na hÉireann
Government of Ireland

Building Regulations

Technical Guidance Document C

Site Preparation and Resistance to Moisture






Amended 2023

Prepared by the Department of Housing, Local Government and Heritage
go.w/housing

Typical Non-Compliance Issues found in KCC

Miscellaneous:

TGD Part K & Part M



Things I think could be improved would be...

- ▶ Building Control authorities to provide workshops for designers. To encourage better compliance with drawings, calculations, specifications and inspections.
- ▶ Additional good guidance to Homeowners regarding Opt Outs. As part of improving compliance with Building Regulations KCC currently issue standard email to all valid Opt Out CN, which includes list of typical compliance items as well as good practice guidance, useful links, sample list of ancillary certificates required for buildings or works.
- ▶ Improved communication between Building Control authority staff and Assigned Certifiers, Designers, Builders and Owners.

“Progress is impossible without change, and those who cannot change their minds cannot change anything.”

George Bernard Shaw

Thank you